

Lloyd's Register of Shipping.

Ship's Name R.F.A. "EDDYBAY"Official No. 184616

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in DUNDEE.

The following list of ventilators cancels that shown on the C11 Report:-

Forecastle Deck.

1- 9" diam. to Canvas store coaming 36" x 32".

1- 9" " " Bosun's " 36" x 32".

2- 11" " " Dry Cargo Space " 36" x 34".

2- 13½" " " " Hold. " 36" x 36"

2- 9" " " Ballast Pump Room " 36" x 32"

2- 7" " " Diesel Pump Room " 36" x 30"

1- 7" " " Lamp Room coaming 36" x 30"

1- 7" " " Inflammable store coaming 36" x 30"

all ventilators fitted with steel hinged gastight flaps except one ventilator to Ballast Pump Room, which is fitted with one ordinary type plug with gastight cover.

Bridge Deck.

Mechanical ventilation fitted to stores etc at sides, in lieu of 8 - 6" x 4" goosenecks.

1- 13½" diam. to stores etc (5) coaming 36" x 36" fitted with hinged steel gastight flap.

on the port side of the Bridge End an opening about 16" x 10" - 5'0" above Deck is fitted and provided with a hinged steel gastight cover.

Poop Deck.

Mechanical Ventilation fitted in lieu of natural ventilation

Boiler Casing plated over at Poop Deck level .24" diam. escape hatch fitted - admiralty pattern - coaming 6½". steel hinged W.T. cover of strong construction. M.B.S. one toggle.

Boiler Deck. 18" diam escape Hatch fitted to Top of Pump Room Trunk - Admiralty pattern - coaming 6½" - steel hinged W.T. cover of strong construction - manipulated both sides - one toggle.

S. Bowman.

5th May 1952.