

16 MAR 1967

SHIP'S NAME

"NANCHANG"

PORT

AUK

No. 13340

LAST SURVEY DATE

24.2.67.


CLASS IS SUBJECT TO

All starting air pipes except three lengths of main starting air pipes for bottom cyls, being spec. exd. and dealt with as nec. by N.D.D.

Aux boiler, temporary repairs on account of leakage. Tubes expanded and seams caulked. Boiler found tight at 65 psi and S's now adjusted to 65 psi. Recommended Subject to aux boiler being raised to maximum safe working pressure (100 psi) the smoke tubes, throat plate and Ogee ring seams examined for leakage at next A.B.S. but not later than the end of April 1967.

It is submitted that this vessel is eligible for ~~THE~~ ~~RECORD~~ to remain as classed.

Subject as above and now recommended, recommended,



Lloyd's Register
16/3/67
Foundation

004364-004368-0075