

PT

~~COPY~~

Ship's name "ASIA ENTERPRISES ex
SHAUKIWAN"

Port KOB

No. 14868

Class is subject to

Last survey date 5.9.65

NONE

S.R.L. Appendix (as before ~~xxxxxxx~~)

Surveys due

SPECIAL SURVEY (C) due 5.65. Postponement
until 5.66 approved 14.6.65 provided a satisfactory G.E. is
held.

Nature of present survey (afloat and in drydock)

Docking. G.E.

Commencement of Special Survey.

Examination of damage (cause unknown).

Wear and tear repairs.

Is interim certificate in order

Yes/No/None

It ~~xxxxxxxxxxxxxxxxxxxxxxxxxxxx~~ PORTION OF SURVEY HELD:-

EXAMINED:- F. & A peak tanks: Nos. 2, 3, 4 & 5 holds.
Hand pumps & suction: chain cable.

SS proposed to be completed by

Recommendation

SUBMITTED record of DS 9,65 be assigned,
subject to port & starboard bower anchors being
repaired and retested and the spare bower anchor
being replaced by one of Rule size at the earliest
opportunity, to upper deck plates, 1st inboard
from stringer abreast No. 4 hatchway, being renewed
and adjacent plating being examined and dealt with
as necessary, temporary Manilla Rope and wood block
of auxiliary steering gear being replaced by S.W.R.
and block, set up shell plating (p & s) with structure
in way and buckled D.B. floors being specially
examined and dealt with as necessary by completion
of the S.S., but ACTION be DEFERRED for S.S.

DS 9,65 subject.

- SNR.L. APPENDIX (AMENDED)
- (Main structure partly of P.403 Steel).
 - Shell plate K.1, (s.s.a) buckled.
 - (Wavy upper deck to be kept under observation).

IT IS FURTHER SUBMITTED postponement of completion of Special Survey until 5,66 merits the favourable consideration of the Committee.

PUBLICATIONS TO NOTE

S.S. PART HELD

DA. 8/10/65.

SR



© 2020

Lloyd's Register
Foundation