


# COPY LLOYD'S REGISTER OF SHIPPING

Kobe Rpt. 8 No 14868



B-121866

Port

KOBE

Date

6th September, 1965.

**This is to Certify** *that I have*

*surveyed the* **S.S. "ASIA ENTERPRISES"** **7,136 Gross tons** *of HongKong on*  
**ex. "SHAUNKIVAN"**

28th August and subsequently whilst the vessel lay afloat and in drydock at Messrs. Ishikawajima-Harima Heavy Industries Ltd., Aichi Shipyard, for General Examination for Postponement of special survey (C) due May, 1965 until May, 1966; Commencement of special survey (C) due 5 /65 and Damages, times and causes stated unknown

*and that I am transmitting to the Committee of Lloyd's Register of Shipping, London, a report, stating that all repairs recommended by me have been completed to my satisfaction, also that I am*

*recommending that she be* continued as classed with fresh record of drydocking 9/65 and that special survey (C) due 5/65 be postponed until May, 1966 subject to : Bowed shank and stopper pin (port anchor) and bowed stopper pin (starboard anchor) being repaired by S.S. 5/66 and oversized spare anchor being replaced by Anchor of Rule size by S.S. 5/66; Thin strength deck plates first inboard from stringer abreast No.4 Hold Hatchway (P & S) being renewed and adjacent deck plates being specially examined and dealt with as necessary S.S. 5/66; Temporary Manila Rope and Wood Blocks forming part of Auxiliary Steering Gear being replaced by S.W.R. and suitable blocks S.S. 5/66; Buckled Double Bottom floors being specially examined and dealt with as necessary S.S. 5/66; shell plates from aft Keel No.4, A10 (port) set up, B10, P5, H6 and Q14 with bulkhead in way (port side) set in, P18 and fore peak frame in way set in (now temporarily doubled), G9 (starboard) set in all being specially examined and dealt with as necessary S.S. 5/66, and to any other outstanding conditions of class being dealt with as previously recommended.

- P. T. O. -

*J. R. G. Smith*  
Surveyor to Lloyd's Register of Shipping

J. R. G. Smith

## KEY TO ABBREVIATIONS

AS Annual Survey  
BiS Biennial Survey  
DS Docking Survey  
NS Cargo Battens not fitted (No Sparring)

SS Hull Special Survey  
SS(Dr) Hull Special Survey (Drilling)  
SS(M) Hull Special Survey (Modified)  
CSH Hull Special Survey (Continuous)

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :-  
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

(Cert. B) 3,65 KOB

004369-004373-0133

FOR LONDON

© 2020  
Lloyd's Register  
Foundation



