

	Equipment	Numerical.	
L(B+D)			= 39603
Midship deckhouse	= 30.25 x 7.5 x .50		= 113
Casings	20.50 x 7.5 x .50		= 77
"	50.00 x 10.5 x .50		= 262
After deckhouse	31.00 x 7.5 x .50		= 116
	= letter "af"		40171

2 bowler anchors - stockless - each @8cmts.
3rd bowler anchor omitted.
Stud chain cable 225 fths @ 2^{1/2}lb
reduced length per Ministry of Shipping Cte?
Stream Anchor stockless 234 cwt.
Stream Wire 30 fths. 5 6x12 F.S.W.
Tow Line 120 fths. 4 3/4 6x24 spec F.S.W.
Hawser 2 @ 90 fths. 2 1/2 6x12 F.S.W.
Warps 2 @ 90 fths. 2 1/2 6x12 F.S.W.

See letter

MIDSHIP SECTION

PLANS TRANSFERRED
TO SISTER VESSEL

"NEED"

RECORDS DEPT.
LONDON.



© 2020

Lloyd's Register
Foundation

Cellis

J. L. Thompson Sons'

YARD No. 620

621, 622, 623 10.2.42

624 15.4.42

PLANS TRANSFERRED

TO SISTER VESSEL

NUNEZ DE BALBOA


Midship Section

Thistle Dale

NO. 33503.

NO. 338104

RECORDS DEPT.
LONDON.



004369-004373-0282



© 2020

14/N Polegate

Register
Foundation

W. J. Wood.

W. J. WOOD