

Lloyd's Register of Shipping.

Ship's Name

"THISTLEMUIR"

Official No. 169034

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

ADDITIONAL ACCOMMODATION NO. 5 TWEEN DECKS. P & S.

ESCAPE HATCH Shelter Deck, Port side. Opening in deck 21" x 21". Hatch coaming 2'0" x 2'0" x 30" high, 3/8" thick, with hinged steel W.T. cover
Hatch coaming electrically welded to deck plating.

VENTILATORS. Port side. 2 @ 9" dia. Coamings 30" x .32 fitted with wood plug and canvas cover.
Starboard side. 1 @ 6" dia. Coaming 30" x .32 fitted with wood plug and canvas cover. 1,6" swan neck ventilator fitted with canvas cover.

SIDE SCUTTLES Starboard side. 2 additional side scuttles 10" dia. with hinged deadlights.

W.C. DISCHARGE STARBOARD. W.C. discharge led into original W.C. discharge - the ship's side valve of which is controlled from above the freeboard deck.

WASH BASINS. Wash basin discharge led into original discharge pipe fitted with valve controlled from above the freeboard deck.

W.T. DOORS. Fitted on aft tween deck bulkhead, port and starboard.

George Fullerton.

GLASGOW, 28th January, 1944.

*(Wokingham)**Noted.*
17 FEB 1944
A.P.S.