

Ship's Name ~~SS~~/MS "NORMANBY HALL" LR 525635  
 Gross tons 332 Port of Registry Chester Port Liverpool  
 Date of build 1943 7 Is there a Rpt. 9? Yes Rpt. No. 166690  
 No. of visits 3 First date 8/6/65 Last date 11/6/65  
 Interim Cert. issued & copy herewith? Yes Damage rpt. issued & copy herewith? No Last rpt. (H.Q. only) 21V.166333  
 Date of completing rpt. 12/7/65 Surveyed at, if different from Port above Ellesmere Port  
 Surveyed afloat and/or in D.D. Both Last date of examination in D.D. 8/6/65  
 Has a Load Line Survey been held? Yes Summer freeboard as verified 1' 2<sup>3</sup>/<sub>4</sub>" ✓

State which additional Rpt. 8 is attached: (Cont); (PS); (DP); (EQ); (RIS)

Survey fees Damage fee Expenses  
 Rky £5 £3 £3-3-0  
 Rpm £4 S.A. fee ✓ 34

I have surveyed the above-named ship in accordance with the Rules for Damage and Docking Survey

Damage : Cause and date unknown

Now Done : On examination found on P.S. in way of No.1 hold shell plate No.2 (from forward) in 1st below sheer set in but found to remain efficient, it is therefore recommended that 'shell plate No.2 (P.S. from forward) in 1st below sheer set in' be made an entry in the S.R.L. Appendix.

Wear and Tear : Welded butts of 4 in No. frames in holds, found fractured were veed and rewelded satisfactorily.

Buckled and torn bracket between hatch end beam and side coaming at aft end of No.1 hatch was renewed satisfactorily.

Steering gear sheaves and pins examined and found satisfactory.

Steering chains examined, annealed, tested and found satisfactory.

Steering gear tested by swinging rudder P.&S. and all found satisfactory.

Minor repairs to rails, doors, hatches etc all satisfactorily completed.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated. I recommend, therefore, that this ship remain as classed with/without fresh record of dry docking 6,65 subject to any outstanding conditions of class being dealt with as previously recommended.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Date of Committee LIVERPOOL - 3 AUG 1965

Minute

DS 6,65

David B. Henderson  
Surveyor to Lloyd's Register of Shipping

David B. Henderson

ALSO FOR
SPL FOR
TRO
SRL
POSTING
HEADER
CERT

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

date of the next Special Survey. Where repairs have been effected or it is considered that re-examination or repairs should be made before that date the circumstances and

The condition of any item is to be described as "good" only when it has been examined, found or placed in good condition and is considered to be acceptable until the due

Rpt. 8 (P.S.) DRY CARGO SHIP

Ship's Name <del>SS</del> /MS	"NORMANBY HALL"	Port	Liverpool
S.S. ( ) Due		Rpt. No.	166690
In dry dock from	8/6/65	In dry dock to	8/6/65
	<u>Examined &amp; condition</u>		<u>Examined &amp; condition</u>
Shell plating	Good	* Air & sounding pipes	Good
Sternframe	Good	Doublers under " "	-
Rudder	Good	Steering arrangements (main)	Good
Was rudder lifted?	No	" " (aux)	Good
Plating, etc. in way of shell openings	Good	Windlass	Good
Side scuttles & deadlights	Good	Masts & standing rigging	-
Overbd. scuppers & discharges	Good	Hand pumps & suction	Good
F.P. spaces	Good	W.T. doors	-
Chain locker	-	Bulwarks, freeing ports, etc.	Good
A.P. spaces	Good		
Engine space	Good		
Boiler space	-		
Under E. & B.	-		
Coal bunker	-	<u>EQUIPMENT:</u>	
Tunnel & well	-	Equipment letter	d
Cement, asphalt, etc., on btm. shell	-	Fee ltr., if diff. from eqpt. ltr.	-
Weather decks	Good	Anchors: No. on board	2B 1S
* Casings	Good	State if ranged	No
* Deckhouses	Good	Length on board	Stated complete
* Superstructures	Good	Mean dias. range from	to
* Skylights	Good	Rule length	Dia.
* Companionways	Good	Mooring ropes	Good and sufficient
* Hatchways	Good		
* Ventilators	Good		
Other items:			

\* These items to include their closing appliances  
Where a part Special Survey and, say, Dry Docking Survey are held at the same time, the items for SS should be marked "For SS"