

## Lloyd's Register of Shipping.

Ship's Name "BRIGHTON"

Official No. 169168

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in

ADDITIONAL ACCOMMODATION IN No.5 TWEEN DECKS. PORT SIDE.

ACCESS HATCH, SHELTER DECK ABREAST No.5 HATCHWAY. PORT SIDE.

COAMING 18" x .40" With hinged steel W.T. Cover secured by toggles.

VENTILATION. 1 Vent 12" dia. coaming 33" x .32 with wood plug and canvas cover.

2 Swan neck ventilators 6" dia with canvas covers.

SIDE SCUTTLES. 7 @ 10" dia of strong construction and fitted with hinged  
deadlights.

DISCHARGES. 1 - 4" Soil pipe, Baltic type W.C. with storm valve on ships side.

1 - 2" Scupper and wash basin discharge fitted with double  
automatic self closing valves, easily accessible.

George Yulland.

GLASGOW, 15th SEPTEMBER, 1943.

Noted.

(Wokingham)

21 SEP 1943

arrangement  
accom  
removed  
Call (015) 28646  
See