

Ship's name

SAFINA-E-JAMHOORIYAT

Port

Karachi (SA 173) JUN 1963

Last survey date

Class is subject to

- ① aft main feed-pump water-end valve-chest being renewed by 1/63 (5 hrs.)
- ② B&H centre & inboard main feed-pump water-ends being renewed by 4/63 (4 hrs.)
- ③ all boilers being repaired as necessary at Karachi wharveship board.

M.B.S. (due 3/63) not commenced. Repairs.

SRH (Lib 1) "Aft (outboard) main feed pump repaired, water end cropped & part renewed, false landing fitted to S & D valves; the Surveyor recommends that the outboard feed-pump water-end be specially examined by 5/64 (12 hrs. limit).

Item ② Both pumps dealt with by renewal & to be deleted.
SRH application Eschaust-turbine thrust-collar repaired & to be deleted.

Item ③ / all superheated elements removed from all boilers.
cross / all plain tubes in Port, centre & fwd. boilers and also some air-heater tubes removed. Some air-heater tubes in Port and Fwd. boilers found wasted and safety-valve of Fwd. boiler found leaking. Forced draught fan engine remote controls missing. The Surveyor recommends that the Port boiler air-heater tubes be dealt with at the earliest opportunity and the Fwd. boiler air-heater tubes (wasted) and its safety-valves and the forced-draught fan engine (wasted) be dealt with at the earliest opportunity.

(2)

17 JUN 1963

Ship's name *SAFINA-E-JAMHORIYAT*Port *Kasachi*

No. 144

Class is subject to

Last survey date

remote-control be dealt with at Chittagong whence
ship now proceeding.

It is submitted that the
 vessel **WILL BE** eligible
 for the record MBS. 5/63
 when the survey has been
 completed, by repairs to

P. & Ford. boiler air-heater tubes,

Ford. boiler safety-valves,

forced-draught fan engine remote controls

subject as now amended re
outboard main feed pump,
and re boilers.

Note for SPL. Amend aff main feed pump to outboard main feed pump.

Note for SPL. Appendices. Delete item re L.P. turbine.

Note for RB } Delete re boilers: - SPL.
& her det. }

NOTED FOR
 POSTING

Lloyd's Register
 Foundation

17/6/63