

- 8 JUL 1965

Ship's name

"COPTIC"

Port C.Tn

No. 7347

Last survey date 9.6.65

Class is subject to

1. E.G. boiler not being used until surveyed.
2. Port forward main sea inlet and starb'd ballast sea inlet valves being specially examined at next dry-docking.
3. Repairs to entablature of starb'd forward diesel generator engine being specially examined by the end of 11/65
4. S.A. generator engine (M/L repairs) to cylinder jacket being re-examined by 11/65.

Windlass Damage.

Whilst heaving up anchor, windlass cheeks were broken and several teeth of gear-wheel also broken. Cheeks now metalocked and pegged teeth fitted to the gear-wheel. Windlass found satisfactory under working conditions on completion. Surveyor recommends windlass cheeks in way of primary pinion bearings and 1st reduction gear-wheel being further examined and dealt with as found necessary by the end of September, 1965.
(3 months)

It is submitted that this vessel is eligible to remain as classed, subject as above and as now recommended.



© 7.7.65

Lloyd's Register
Foundation