

LLOYD'S REGISTER OF SHIPPING. 23 JUL 1941

Ship's Name "COPTIC".

Official No. 149312.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Additional accommodation has been fitted in shelter tween decks in vicinity of previous tonnage space. ✓

A steel companionway has been fitted over old tonnage hatch 1- 8'-0" x 2'-6" x 7'-6" high with hinged wood door of substantial construction 5'-6" x 24" with 24" coaming. 4 sidelights with deadlights of substantial construction fitted on port side of tween decks. ✓

Lavatory and washbasin discharges fitted with automatic/non return valves operated from above freeboard deck. ✓

1 vent 3'-0" x 12" dia. (cowl);

2 " 3'-0" x 6" " (G.N.); and

1 " 3'-0" x 4" " (G.N.) all fitted to new accommodation.

1 vent 2'-6" x 12" dia. (Mushroom) fitted to after generator room.

1 vent 2'-6" x 12" " " " forward " " .

all of substantial construction and supplied with efficient closing appliances. ✓

Noted
W.R.
24 JUL 1941

W.R. Robinson 15/7/41.
SURVEYOR TO LLOYD'S REGISTER.