

28 MAY 1932

Ansd. X

should be reported
on the full
breadth of vessel
wale.

C. 7c, 1128.

FREEBOARD REPORT on the M. V. HOPE MOUNT

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to


- (1) The airpipes to the Cofferdams being increased in height to 36". Effluent means of closing being provided for all air pipes, except those on the forecabin to the forward deep tank, having gauge over.
- (2) Additional longitudinal strength being afforded to the gangway by the fitting of stringer angles on each side at the top.
- (3) Open rails being fitted for at least half the length of the exposed portion of the weather deck, or alternatively the freeing port area being increased to $170\frac{1}{2}$ sq. feet in the after well & $88\frac{3}{4}$ sq. feet in the forward well on each side of the ship.

signature
of Owners & Val.

30/5/32

CONVENTION.

004440-004449-0082



© 2021

Lloyd's Register
Foundation

7-8-
7-2-