

20 DEC 1946

Id. 2676

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

"MASTROMITSOS"

Ship's Name ^{ex} "REMBRANDT".

Official No. 168048

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have been effected to entitle the vessel to assignment of freeboards as an Open Shelter Deck Ship:-

- (1) Tonnage opening in shelter deck restored and closed by efficient temporary covers. ✓
- (2) Apertures P. & S. in tonnage well after bulkhead permanently closed by steel plates. Openings in forward bulkhead of tonnage well P & S restored to storm boards (3") in riveted channels for full height. ✓
- (3) No scuppers to hold bilges fitted in shelter tween deck. ✓
- (4) Drain holes cut in wings of shelter tween deck bulkheads to permit of efficient drainage. ✓
- (5) 5" diameter valves fitted on overboard scuppers P & S from tonnage well with extended control to upper deck. ✓
- (6) The drop handle self closing cocks fitted to the 4 scupper drain pipes from the shelter tween deck, fwd. & aft, and led to the machinery space overhauled and placed in good order. ✓
- (7) D.E.M.S. accomodation within shelter tween deck, P & S, abreast No.5 hatch now removed and sanitary discharges therefrom permanently closed. 6 side scuttles in way of this accomodatiin dispensed with and apertures closed by riveted & E.W. spigot plates. ✓
- (8) 4 additional side scuttles with hinged deadlights fitted in way of crews' messroom in poop. ✓

A. R. Lucas
SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING, HULL.

12th October, 1946.

*Noted
EJ
20 DEC 1946*

ML-D



© 2021
Lloyd's Register
Foundation