

date: June 28 July 1.2.4.7.9.11.12. 1941

18 JUL 1941

Index No.

33426

Lloyd's Register of Shipping.

Ship's Name "KANA"

Official No. 161120

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in Hull on 16.8.40

The Shelter deck has now been made the foreboard deck by the following alterations also a new certificate and copy issued after amending foreboard marks:-

1) The tonnage opening in the shelter deck, the freeing ports in the tonnage well and all overboard scuppers from the shelter tween decks including those in the tonnage well have been permanently closed.

✓ The tonnage opening has been suitably stiffened and covered by existing wood hatch covers bolted to above and caulked.

Steel companionway ($\frac{3}{8}$ th.) for access to gunners accommodation fitted to port side of tonnage opening and closed by steel hinged door with lock operated both sides.

Magazine steel hatch (21" size) fitted to starboard side of tonnage opening and covered by $2\frac{1}{2}$ " wood cover secured by cleats, tarpaulins, wedges & battening bars.

2) Discharge from wash-basins overboard in gunners' accommodation below the shelter deck fitted with screw-down automatic non-return valve controlled from the shelter deck.

3) Suitable provision has been made for rigging lifelines which are available in all parts of the ship which might have to be used by the crew in the regular working thereof.

4) The watertight bulkheads have not been extended to the shelter deck and a notation will thus be required to be made in the Register Book regarding their omission in the tween decks.

5) The Shelter tween decks are now drained port and starboard by 3" galvanised steel pipes to the aft end of no 2 hold bilges and to the forward end of no 4 hold bilges.

6) Additional ventilator fitted on machinery casing top to ventilate saddle back & tween deck bunker space - 21" dia x 3'-0" coaming covered by cowl & wood plug & canvas cover as required.

On starboard side of poop 2.8" cowl & 1-3" goose-neck ventilator fitted (3'-0" coaming) and covered by wood plug & canvas cover. Four 10" sidelights with deadlights fitted to starboard side of gunners accommodation.


New Certificate & copy with copy of C11 (Contd) put on board.

Noted

S.W.B.

2/7/41

to S. Shields.



Lloyd's Register Foundation