

Delfshaven

John Readhead & Sons Ltd., South Shields. Yard No. 528

F.E.
(FBD.)

1m.9.37.

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME s.s. "EMPIRE HAZLITT" Rpt. Nwc. No. 100567

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement." - Extract from Sub-Committee's Report, 24/5/92.)

D to W dk 37.67' (flat sheer), D to 2nd dk 28.67' (flat sheer), D for scantlings 35.75' to normal sheer. Depth "d" -
1st Long. No. 15194)
2nd Long. No. 38994) to normal sheer Proportions = $\frac{L}{D}$ 11.27
Framing Bulb angle framing as approved Sheerstrake As approved

This partly fabricated Standard Ship Type "B" is a sister vessel to the "EMPIRE SQUIRE" and "EMPIRE FOREST".

The draught is about 6" less than that corresponding to the freeboard which could be assigned as a F.S. vessel.

The tank top plating increased under hatchways in lieu of ceiling.

This vessel appears to have been built in accordance with the Rules and the approved plans, and it is submitted she is eligible to be classed 100AL "With freeboard"

The Summer Freeboard as shown on the attached extract from the Freeboard Verification Form, now marked on the vessel's sides, to be inserted in the classification certificate and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying extract, to be inserted in the certificate of classification.

2 Dks
Cell DB 367' 1260t, FPT 110t, APT 105t
FK, 7BH (Coll to W dk, 6 to 2nd dk); 6 divisional W.T. BHs in 'tween decks, pt. Cem., Lloyd's A & CP.
Q.L. 446.4' E.S.D.

a The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed, and that hatch covers at the 2nd deck and cargo battens will be fitted at the first available opportunity.

Insert in S.R.L: (A bower anchor and 45 fathoms of chain cable to be supplied). Hatch covers at the 2nd deck and cargo battens to be fitted at the first opportunity.

The Surveyors should be informed *it is* concluded the diameter and spacing of the rivets in the butts of the keel plating and the thickness of the 10" bulb angle stiffeners of the collision bulkhead have been approved as reported.

004459-004465-0091

30.7.42.

