

Fld. 1981.

36863

## Lloyd's Register of Shipping.

4 JUN 1943

Ship's Name "AELBERT CUYP" (ex "EMPIRE HAZLITT") Official No. -  
"N.N. DELFSAVEN"

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations now done:-

In way of alterations inside forecabin:- 1 additional ventilator fitted on upper deck, 12" diameter, substantial coaming, 3'-0", with wood plug and canvas cover.

In way of new accommodation in shelter deck amidships:- 2 temporary wood companionways, 5' x 5' x 6' substantially constructed, fitted on No. 3 hatch, one port and one starboard, leading to shelter deck. Hinged wood doors with spring lock. Hatch covers, tarpaulins and battening arrangements suitably adapted.

In way of new accommodation in after shelter deck:- 7 - 7" diameter ventilators fitted on upper deck leading to shelter deck spaces, substantial coamings 3'-0" high with wood plugs and canvas covers.

10 additional sidelights fitted in starboard side of after shelter deck spaces each 11" diameter with hinged deadlights.

2 additional sanitary discharges fitted in starboard aft corner of shelter deck with storm valves and screwdown non-return valves.

New companionway fitted on upper deck adjacent to starboard after corner of No. 5 hatch; strongly constructed of  $\frac{1}{4}$ " E.W. steel plate, with sill 27" high, hinged wood doors with spring locks.

Additional access provided from inside mainmast house. Sill of existing steel door extended to 24" and cut beam suitably compensated.

A. W. B. Edwards

SURVEYOR TO LLOYD'S REGISTER.

SURVEYOR TO LLOYD'S REGISTER.

H U L L.



© 2020

Lloyd's Register  
Foundation