

Lloyd's Register of Shipping.

Ship's Name "AL HUSAINI" (ex "Mont Clair")

Official No. 180033

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in August 1943.

NOW DONE:- Additional lavatory installed in Engineers' deckhouse above the level of the freeboard deck, having sanitary discharge fitted with ^a3" diam. automatic non-return valve at ship's side in tween deck space, port side, in an accessible position forward of fresh water tank.

Steering gear hatch removed and aperture in upper deck permanently closed with welded plate. Poop deck house extended aft approx. 7'-6" to provide lavatories and toilet facilities for native crew. Sanitary discharge fitted with 4" dia. double automatic non-return valve at ship's side in steering gear space, starboard side.

Original lavatories in crew's accommodation aft, below the level of upper deck, permanently removed together with two S.D. automatic non-return valves in way of No. 5 hold, starboard side, and openings efficiently closed.

D. J. Archibald

Surveyor to Lloyd's Register,

Montreal, P.Q.

11th. June 1948.

No copy of this Report has been placed on board the Vessel, being of Canadian Registry.

Noted
[Signature]
14 JUL 1948



© 2021

Lloyd's Register Foundation