

Ship's name

Anthony

Port

halta.

No.

2.856

Class is subject to

Nil

Last survey date

19.7.63

30 AUG 1963

Docking w/o .315", rewooded, clearance .050"
T3(CL) due 5.63, now held. (Damage).
MBS due 5.63, now held.

The Surveyor states screwshaft cracked at forward end of keyway on both sides to a length of 2 1/2" (Liberty type). Ships spare screwshaft, corroded on cone, machined & crack detected before fitting. Propeller blade edges faired.
Main condenser end door heavily corroded & now renewed.

It is submitted that this
vessel is eligible to remain
as **CLASSED**. MBS & T3(CL) N 60d 7.63 now



30/8/63
© 2020

Lloyd's Register
Foundation