

~ Sir James Clark Ross ~

Convention

Forecastle not less than 7%  
Height not less than standard

Ship as built

Forecastle = 20%

Casings - protection -  
entrances to height of sills

Casings protected by poop  
- Sills on Poop deck 15" as per rule

Gangway

Protection of Crew, Access to Machinery Sp

No  
but high deck platform +  
passageway for crew in deep Lw dls

Hatchways

Steel covers generally but  
forward cargo hatch - wood covers

Facing ports Open rails for  
 $\frac{1}{2}$  L of exposed portion of  
weather deck

Ports = 63 ft in length 268"  
but bulwark on weather deck  
is on relatively high platform

W.T. Bulkheads

Collision BH to upper deck  
Forward Cofferdam BH " "  
BHs in oil tanks to 2nd "  
Forward Machinery BH to upper deck  
After " " " Cabin deck



© 2020

Lloyd's Register  
Foundation

004486-004488-0200