

C
RNC

ELT

SURVEYOR OSLO

~~REGISTERED VESSEL~~ (19.8.66)

SIR JAMES CLARK ROSS REURLET 16TH CERTIFICATE MAY BE ISSUED FOR
SHIP PROCEED UNDER OWN POWER IN BALLAST AS CLASSED VESSEL PROVIDED
GENERALLY EXAMINED IN DRYDOCK INCLUDING SELECTED SIDE AND CENTRE
CARGO TANKS AND EXAMINATION NOT LESS THAN CIRCULAR 1959 STOP ANY
BOILER LIKELY TO BE USED SHOULD BE SURVEYED THROUGHOUT AND SAFETY




© 2020

Lloyd's Register
Foundation

004488-004488-0227^{1/3}

VALVES ADJUSTED STOP PROVIDED WEARDOWN BOTH SCREWSHAFTS SATISFACTORY
AND PROPELLERS BACKED OFF FOR EXAMINATION CONES SHAFTS NEED NOT BE
DRAWN STOP GENERAL EXAMINATION ALL MACHINERY SHOULD INCLUDE WINDLASS
AND SPARE GEAR AND SHORT SEA TRIAL STOP ONE JOURNAL AND BEARING OF
EACH MAIN ~~XX~~ ENGINE REQUIRES OPENING OUT AND REMAINDER CHECKED BY



© 2020
Lloyd's Register
Foundation

CRANKSHAFT DEFLECTIONS WRITING MORE FULLY



COMMITTEE

© 2020

Lloyd's Register
Foundation

0227 3/3