

8 NOV 1950

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "BARON YARBOROUGH" Official No. 160125.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

See LL 4D No.457.

Forecastle. Forecastle bulkhead, all openings closed and new tonnage opening made - opening 5'-0" x 4'-0", coaming 18" high and closed by means of channels and 3" thick weather boards.

Wing W.C. houses removed with exception of overhang of forecastle deck.

All ventilators on forecastle deck removed except 4'-9" diameter cowl ventilators (.32" thick coamings 36" high fitted with wood plugs and canvas covers).

Forecastle T.D. space now becomes cargo space.

Poop. Poop T.D. space now converted to crew accommodation space.

Poop bulkhead now intact.

Poop Deck cargo hatch removed, opening plated over and new steel deckhouse erected.

Poop Deck now wood sheathed (2½" thick)

Companionway:- Access to poop T.D. accommodation by means of 2 stairways inside new steel house.

2 openings in steel deck house each 5'-0" x 2'-0" with 18" coamings (i.e., 15½" above wood deck) and closed by means of wood hinged doors operated from both sides.

Poop T.D. Sidelights:- 2'-16" diameter and 10'-12" diameter of approved pattern and each fitted with C.B. deadlight.

Ventilation - on Poop deck 11'-6" diameter M.Vs to T.D.

accommodation with W.T. screwed caps operated from outside and each fitted with canvas cover.

D. B. Book:

SURVEYOR TO LLOYD'S REGISTER.

7th November 1950.

G.H.W.

9 - NOV 1950

