

## Lloyd's Register of Shipping.

Ship's Name "BURY"

Official No. 132093

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

ALTERATIONS.

HATCHWAYS :- Hatchway N° 1 and 2 permanently closed by steel plates riveted to existing Hatch webs which have been raised to level of coaming, coaming having steel angles riveted all round to carry steel plates.  
All work caulked and made watertight.  
1 small access hatch (opening 26" x 26") fitted on top of N° 2 Hatchway (S.S.F.) with bolted W.T. steel cover.  
After bay of N° 2 Hatch arranged to hinge forward, hinged cover packed, secured by bolts and made watertight.

SANITARY DISCHARGES :- Two additional sanitary discharges from WCs. in tween decks, led overboard below Freeboard deck and fitted with Brass Storm Valves at ship's side

Alexander P. Moore.  
Glasgow, 20<sup>th</sup> April, 1943.

A copy of the above has been attached to the copy of the C. 11. report on board the vessel.

notes

S.W.B.

27 APR 1943

(Wokingham)

Cancelled