

NG ARRANGEMENT Endorsement.

Builders: Messrs. *1/2 Indira & Bassett Type Trawler "Calcutta"*
Yard No.

Engineers: Messrs.

Engine No.

Surveyors: Messrs.

Classification

It is submitted that the plan of *General*
Pumping Arrangement

merits approval, provided the arrangements be as

shown and amended on the plan and the remaining

requirements of ~~Sections 20 and 24 of the Rules~~ *for Pumping and Piping* ~~(19~~

be complied with so far as they are applicable.

*It is concluded that the ~~arrangement~~ of bilge pumps and bilge
suctions in the machinery space ~~is~~ as originally fitted.*

*With reference to the last paragraph of the
Surveyors letter the existing high level suction and
service lines could be retained provided the suction
line is used for bilge drainage purposes only.
The service line should be used for pumping out
and filling compartments used for the carriage
of water ballast.*

*All suctions should be connected by permanent
pipes to the service and suction line and all valves
on these lines should be so arranged as to be
readily accessible at all times*

*If the existing lines are retained a revised
plan of pumping arrangements should be submitted
for consideration.*

Plans 2

in copy. 1

m. 8.36. T.

Its 28/9



© 2020

acc.

26/9/50

Noted AR

Register
Foundation

004527-004533-0205