

004564-00
-2-
12

No. 512

Lima 16th September, 1957.

Lb, dr

113391

SURVEY REPORT

THIS IS TO CERTIFY that at the request of Messrs. H. M. Messure & Co., Lloyd's Agents, Lima, the undersigned Surveyor did proceed on board the Single Screw Steel S.S. "MABANG" 3369 Gross Tons, of Callao, whilst she lay in the Naval Arsenal Dry Dock in the Port of Callao, on the 15th September, 1957, in order to ascertain and report the nature and extent of damage stated to have been sustained to shell plating.

Upon examination the undersigned:

FOUND:

HULL

Vertical fracture open to sea 2" in length in way of shell plating in starboard side, Strake H, plate No.5, at heel of Frame No. 97.

RECOMMENDED:

Temporary repair. To place cement box of appropriate dimensions in way of affected area between Frames Nos. 96, 97 and 98.

NOW DONE:

The temporary repair has now been carried out in accordance with recommendations. Hose test proved satisfactory.

As the vessel is to be placed in Dry Dock for Continuation of Special Survey in the month of November further examination of steel plating in way of affected area will be carried out and dealt with according to findings.

In the opinion of the undersigned this vessel is in condition to proceed on her voyage.

E. Bevan

E. Bevan
Surveyor appointed by Lloyd's Agents.



© 2021

Lloyd's Register
Foundation

004564-004572-0203

as I
ified }
or pl
rine a
aces,
ins,
94.1
tom t
ers,
sted
e Bol
M.
w Felt.)
Month
&c.
ascert
vedges r
ter
of 3-
if now
70 F
board) 2
ngth 2
rps
unning
Book
d and
od. a
8,5