

Exhaust Steam Turbines for the  
"ELISABETH MAERSK" & "JOHANNES MAERSK"  
proposed by Messrs. Atlas Maskinfabrik.

IT IS SUBMITTED that with an exhaust steam turbine  
developing 250 BHP at 4000 r.p.m. and geared to a wheel  
shaft running at 345 r.p.m., the following sizes of shafting  
merit approval in accordance with the usual practice, viz:-

Pinion shaft ..... 65 mm. dia. at bearings.

Wheel shaft ..... 100 mm. " at driving end.

Turbine shaft ..... 65 mm. " at bearings.

Further, the particulars of the materials of the  
turbine shaft, turbine wheel, pinion shaft and bandage rings  
are such as could be accepted.

The Copenhagen Surveyors should be asked to forward  
plans showing the method transmitting the power from the  
exhaust turbines to the straight shafting of the  
reciprocating engines. Further, details of the total  
maximum horse power developed by exhaust turbine and  
reciprocating engine, when working in conjunction with one  
another, should be stated, also the corresponding revolutions  
per minute of the propeller shaft.

The Surveyors should also state whether it is  
intended to use the existing straight shaft for the exhaust  
turbine installation.

*[Signature]*

G.H.F.  
6. 9. 34.

*[Signature]*

X

plans  
copies



© 2021

Lloyd's Register  
Foundation

004579-004590-0297