

# Lloyd's Register of Shipping. 11 SEP 1941

Ship's Name M/V "PONTFIELD"Official No. 165780

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in and Certificate No. 15443 issued London Nov. 1, 1939

(Copy of Freeboard report not on board)

Alterations now carried out to provide accommodation for ten (10) additional defense men.

Accommodation situated on starboard side of center (bridge space) castle.

A new fore and aft offset steel bulkhead extending from forward and aft bulkhead casings of center (bridge space) castle consisting of 1/4" thick slice plating stiffened by 3" x 3/8" flat bar irons spaced at 30" centres and electric welded to existing vertical channel pillars, bridge deck beams and the upper deck plating.

Two additions 12" dia. brass portlights, one in forward and one in aft bulkheads of center castle casings, installed with deadlights. A 20" x 20" escape hatch through deck above now provided with trap door and a ladder capable of being stowed against deck head, fitted with hinges.

Toilets; washbasins, galley sink, lockers, air and heating arrangements with exhaust fan and vents as required installed and all overboard discharges with adequate shut off and shipside storm valves fitted.

The portable steel tonnage door through after bulkhead of center (bridge space) castle on starboardside now permanently closed in by electric welding and a new regulation steel watertight door with strong frame fitted and operatable from both sides.

C. Hastie

Surveyor to Lloyd's Register of Shipping

Fee - \$50.00

June 27, 1941

Noted  
12/9/41

The above is now cancelled  
see note letter 4/6/42