

24 JUN 1963

Index No.

(For London Office use)

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "PATELLA"

Official No. 181531

Port of Registry LONDON

This ship has been under survey at IMMINGHAM

63

on the 17th April, and subsequently 195~~x~~ and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~—

Conversion to Composite Carrier

In accordance with Approved plans and Secretary's letters dated 24.1.63 and 1.4.63, existing access hatches to Port and Starboard wing cargo tanks, from forward, Nos. 2,3,4,5,6,7,8 and 9 have been replaced by hinged steel O.T. hatches 5' x 2' with 2'6" coamings x .50" and toggles.

No. 1 Wing Cargo tanks

The existing 2' Diameter access hatch openings to Port and Starboard No. 1 wing cargo tanks have been retained, but hinged steel O.T. covers with 2'6" coamings x .50" and toggles have been fitted.

Additional 2' diameter O.T. hatches with 2'6" coamings x .50" have also been fitted at fore end (1P. 1S)

Butterworth Openings

Standard Butterworth openings 12" diameter have been provided for Nos. 2,3,4 6,7,8 and 9 Wing Cargo tanks (P & S)


Tonnage The Nett Tonnage figure now assigned is 4830.88

*N. Clive Juniper*  
N. Clive Juniper,

SURVEYOR TO LLOYD'S REGISTER  
GRIMSBY, May/63.

forwarded to Owners for placing

A copy of this Report has been placed on board.



24 JUN 1963

38434

Noted  
AR  
26-6-63