

COPY.

# Lloyd's Register of Shipping

NEWCASTLE-ON-TYNE, No. 109128

UNITED WITH THE BRITISH CORPORATION REGISTER



Port SAN FRANCISCO

23rd April 1951.

**This is to Certify** that

E. MARLBOROUGH

the undersigned Surveyor to this Society did at the request of the RAY OIL BURNER COMPANY, attend at their Works in San Francisco, California on the 17th April 1951 and subsequently for the purpose of examining and testing 6 size 6 T.G. Turbine Oil Burners Serial Nos. 51256-51261, Nos. 51256-7 being equipped with "VEE" belt pulleys to enable units to be used for cold starting. Also one 76 A Worthington duplex oil fuel service pump set No. 53068, and Master Controller No. 65F and two duplex oil strainers.

All working parts of the burners have been examined, the rotors balanced, the turbine casings tested by hydraulic pressure to 40 lbs. per sq. inch (twice safety valve pressure), the turbine nozzle boxes, attached piping, valves and fittings tested to 300 lbs. per sq. inch (twice working pressure). The oil end of the oil fuel service pump with attached fittings and strainers was tested to 300 lbs. per sq. inch. All of the above tests were found tight and satisfactory.

Each burner unit has been tested at full speed and found in good working order and, in the opinion of the undersigned, the units are suitable for installation in a vessel to be classed with LLOYD'S REGISTER OF SHIPPING.

For identification purposes the individual items, which have been ordered by Aktiebolaget Pegasus, Stockholm, Sweden, have been stamped as follows:

TURBINE BURNERS

LLOYDS TEST

40 lbs. 300 lbs

EM 21 APR 51

PUMP SET & STRAINERS

LLOYDS TEST

300 lbs

EM 21 APR 51

(Signed) E. MARLBOROUGH

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—  
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."