

24 JUL 1957

Rpt. C. 11 (Contd.)

Index No.

41613

Lloyd's Register of Shipping.

Ship's Name "WEYBURN"

Official No. 153437

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in April, 1957

Nos. 2 and 3 hatches combined to form one hatch.

Dimensions 18'-0" x 18'-0" (Approved plans with Rpt 8)

Coamings. Height above Steel Deck 27" (Sides)

" Thickness (ends 1/2" (Sides)


" Stiffeners (ends 10" x 3-1/2" x .46 B.A.)

" Brackets 3/8" thick with 3" flanges. 5 sides 5 ends.

Hatch Beams Number 7

Spacing 6'-0"

Scantling sketch



Bearing surface and sockets thickness 3-1/2" x 1/2"

Hatch Covers. Material Wood (steel end bands)

Thickness 2-3/4"

How fitted F. and A.

Bearing Surface 3"

Spacing of Cleats 24"

Number of tarpaulins 2

Lashings. Steel locking bars.

J. Taylor

What port has this (cont'd)
Come from Montreal

Noted
JMB
28.8.57.



© 2020
Lloyd's Register
Foundation