

Lloyd's Register of Shipping.

Ship's Name *S. S. "FORT CARIBOU."*Official No. *168485.*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1943.

The accommodation in the tween decks port and starboard sides aft for Gunners now removed. The steel entrance companionway on the upper deck abaft N°5 hatchway removed and opening in deck closed with a steel welded plate. Six 6" dia. cowl ventilators three port and three starboard on upper deck abaft N°5 hatchway removed and openings in deck closed with welded steel spigot plates. Seven 10" dia. side scuttles four port and three starboard abaft N°5 hatchway removed and openings in shell closed with riveted and welded steel spigot plates. Three lavatory discharges one port and two starboard in tonnage well space removed and openings in shell closed with riveted and welded spigot plates. One door port and one door starboard in the bulkhead at forward end of tonnage well removed, existing door openings enlarged to 4'6" x 3'0" having 24" coamings. Welded channels fitted at sides of enlarged openings to take storm boards.

*Alex. M. Jenkins.**Surveyor to Lloyd's Register of Shipping*
LONDON. 5th OCTOBER 1946.*W. J. D. J. D.*
18 NOV 1946

© 2021

Lloyd's Register
Foundation