

Basis computation for C.S. Ship.

Index No. 36127.  
(For London Office only).

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

5

Ship's Name <b>Gloucester.</b>	Official Number	Nationality and Port of Registry <b>British, London.</b>	Gross Tonnage <b>approx 8500</b>	Date of Build <b>1941.</b>	Port of Survey <b>Glasgow</b>
Moulded Dimensions: Length <b>450.77</b> Breadth <b>60.00</b> Depth <b>31.52 assumed</b>				Date of Survey <b>While building May 1941.</b>	Surveyor's Signature <b>A. W. Paterson</b>
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>14690.</b> tons				Particulars of Classification <b>+100A1 with freeboard (centre line)</b>	
Coefficient of fineness for use with Tables <b>.710</b>					

Depth for Freeboard (D).		Depth correction.		Round of Beam correction.	
Moulded depth ...	<b>31.52</b>	(a) Where D is greater than Table depth (D - Table depth) R = <b>(31.52 - 30.05) x 3 = 4.53"</b>		Moulded Breadth (B)	
Stringer plate ...	<b>.04</b>	(b) Where D is less than Table depth (if allowed) (Table depth - D) R = <b>1.51</b>		Standard Round of Beam = $\frac{B \times 12}{50} =$	
Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$	<b>✓</b>			Ship's Round of Beam =	<b>Assumed Standard</b>
Depth for Freeboard (D) =	<b>31.56</b>	If restricted by superstructures <b>✓</b>		Difference	
				Restricted to	
				Correction = $\frac{\text{Diff}^*}{4} \times (1 - \frac{S_1}{L}) =$	<b>Nil.</b>

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...					
„ overhang ...					
R.Q.D. enclosed ...					
„ overhang ...					
Bridge enclosed ...					
„ overhang aft ...					
„ overhang forward ...					
Fore enclosed ...					
„ overhang ...					
Trunk aft ...					
„ forward ...					
Tonnage opening aft ...					
„ „ forward ...					
Total ...					

**C.S.S.**

Standard Height of Superstructure **7.5'**  
R.Q.D. **42"**  
Deduction for complete superstructure **42"**  
Percentage covered  $\frac{S}{L} =$   
Percentage from Table, Line A. **100.00**  
(corrected for absence of forecastle (if required)) **✓**  
Percentage from Table, Line B. **100.00**  
(corrected for absence of forecastle (if required)) **✓**  
Interpolation for bridge less than 2L (if required) **✓**  
Deduction = **42 x 1.000 = -42.00**

## SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product
A.P. ...		1			<b>Assumed</b>		1		
1/4 L from A.P. ...		4					4		
2/4 L „ ...		2			<b>Standard</b>		2		
Amidships ...		4					4		
3/4 L from F.P. ...		2					2		
1/4 L „ ...		4					4		
F.P. ...		1					1		
Total ...									

Mean actual sheer aft =  
Mean standard sheer aft =  
Mean actual sheer forward =  
Mean standard sheer forward =  
Length of enclosed superstructure forward of amidships = **✓**  
„ „ aft of „ = **✓**

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( \frac{75-S}{2L} \right) = -50$   
If limited on account of midship superstructure.

If limited to maximum allowance of 1 1/2 ins. per 100 ft.

<b>Deduction for Tropical Freeboard.</b> <b>Addition for Winter and Winter North Atlantic Freeboard.</b> Depth to Freeboard Deck = <b>31.56</b> Summer freeboard = <b>4.27</b> Moulded draught (d) = <b>27.29</b> Deduction for Tropical freeboard and addition for Winter freeboard = $\frac{d}{4}$ inches = Addition for Winter North Atlantic Freeboard (if required) =	<b>Deduction for Fresh Water.</b> Displacement in salt water at summer load water line $\Delta =$ Tons per inch immersion at summer load water line $T =$ Deduction = $\frac{\Delta}{40T}$ inches =	<b>TABULAR FREEBOARD corrected for Flush Deck (if required)</b> Correction for coefficient $\frac{-710 + .68}{1.36} = 1.39/1.36$ <table border="1"> <tr><td>Depth Correction</td><td>4.53</td></tr> <tr><td>Deduction for superstructures</td><td>42.00</td></tr> <tr><td>Sheer correction</td><td>.50</td></tr> <tr><td>Round of Beam correction</td><td>-</td></tr> <tr><td>Correction for Thickness of Deck amidships</td><td>-</td></tr> <tr><td>Other corrections, scantlings, etc.</td><td>-</td></tr> <tr><td><b>Summer Freeboard</b></td><td><b>51.29</b></td></tr> </table>	Depth Correction	4.53	Deduction for superstructures	42.00	Sheer correction	.50	Round of Beam correction	-	Correction for Thickness of Deck amidships	-	Other corrections, scantlings, etc.	-	<b>Summer Freeboard</b>	<b>51.29</b>
Depth Correction	4.53															
Deduction for superstructures	42.00															
Sheer correction	.50															
Round of Beam correction	-															
Correction for Thickness of Deck amidships	-															
Other corrections, scantlings, etc.	-															
<b>Summer Freeboard</b>	<b>51.29</b>															

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc	...	Tropical Fresh Water Freeboard	...
Fresh Water Line	...	Fresh Water	...
Tropical Line	...	Tropical	...
Winter Line below	...	Winter	...
Winter North Atlantic Line	...	Winter North Atlantic	...