

- 5 NOV 1964

Ship's name Pakistan Promoter Port Kirk Aden No. 585 3839  
 Last survey date 15.9.64  
12.10.64  
 Class is subject to propeller, rubber sealing ring gland studs  
being specially examined as necessary by end of 7.64.

MBS due 7.64 now commenced.

boiler auxiliary feed check valve scantlings reduced  
by constant machining, it is now recommended this item  
be renewed for completion of MBS & by end of 12.64.

Above subject item examined by diver & continue efficient  
the wear down is 7.2 upm. This, now recommended the propeller  
rubber sealing ring gland studs be examined & dealt with as  
necessary and stern bush lining be renewed, both by  
end of 12.64

The Aden Survey reports IP slide valve & gear badly worn  
port vertical side of cast iron valve fitted with a false face & AS  
false faces on casing renewed, top & bottom guide bushes renewed  
& valve rod fitted with a new tail piece.

It is submitted that this  
vessel is eligible to remain  
as CLASSED.

MBS 9.64 on completion subject as above

recommended & as recommended

Appendix Note  
m/e IP slide valve repaired 10.64

To complete MBS F&S boilers & examine throughout  
& then S's adjusted, oil burning system  
& remote controls to examine