

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name " S P A B E C K " Official No. 169593


Port of Registry London

This ship has been under survey at Plymouth

on 22nd August, 1956, and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:—

3, Existing 6" dia. screwdown mushroom type ventilators to cargo tank compartments now removed, a 12"x 12"x  $\frac{3}{8}$ " steel plate doubler welded over deck opening and in each doubler has been fitted a 2 $\frac{1}{2}$ " bore air pipe venting these compartments at a position approximately 18'0" above deck level.

Each air pipe is securely supported from deck and then clipped to the foremast and each open end is fitted with an anti-flame gauze.



Noted  
JMB  
15/9/60

A copy of this Report has been placed on board.

