

Carrying Petroleum in Bulk
M.V. "SIREFJELL" No. 77039 in R.B.

IT IS SUBMITTED the Oslo Surveyors be informed that their remarks have been noted.

It is concluded that the statement that the vessel is now running on the dirty trade implies that oil having a flash point above 150° F is being carried at present.

The requirements of Section 15 of the Rules for Electrical Equipment, which preclude the use of balancer sets as a means of obtaining from a 220 volt source a 110 volt supply for lighting circuits, apply only to electrical installations of vessels carrying oil having a flash point less than 150° F, and the restoration to service of the 220/110 volt balancer set mentioned would accordingly be admissible in the circumstances assumed above, provided the present notation "Carrying petroleum in bulk" were amended to "Carrying oil in bulk F.P. above 150° F".

Sa.

20th May, 1953.

Law.



© 2020

Lloyd's Register
Foundation

004727-004735-0027