

EQUIPMENT		
2 BOWER & ANCHORS	73 1/4 CENTS	EACH STOCKLESS
1 BOWER ANCHOR	73 1/4 CENTS	STOCKLESS
1 STREAM ANCHOR	22 CENTS	EX - STOCK
500 FATHOMS 2 1/2" SIDE CHAIN CABLE	320 1/4 CENTS OR 26 TAYCO CABLE	
150 FATHOMS 1 1/2" STEEL WIRE	5 FLEXIBLE STEEL WIRE	G x 1/2 24
150 FATHOMS 5/4 SPECIAL FLEXIBLE STEEL WIRE	G x 1/2	24
2 HANSEBS	100 FATHOMS 2 1/4 STEEL WIRE	G x 1/2 24
2 WARPS	100 FATHOMS 5/4 STEEL WIRE	G x 1/2 24

M. V. SAN ELISEO

SCALE $\frac{1}{2}$ " = 1 FOOT.

DIMENSIONS:- 460'-0" BP (ON LWL) x 61'-0" MLD x 33'-3" MLD TO UPPER DECK
TO CLASS 100 A.I. AT LLOYDS, CARRYING PETROLEUM IN BULK.
LONGITUDINAL FRAMING AT BOTTOM AND AT DECK.

SCANTLINGS CLEAR OF OIL TANKS TO BE SPECIALLY CONSIDERED
SUITABLE INCREASES TO BE MADE FOR SHEER.

LLOYDS NUMERALS

1 st LONGITUDINAL	N ^o	L x D	= 400'-0" x 33'-25"	= 13295.00
2 nd LONGITUDINAL	N ^o	L x (B+D)	= 400'-0" x (6'-0" + 33'-25")	= 48355.00
7'D TO UPPER DECK			= 400'-0" + 33'-25"	= 13.83
				= 33.25

STEM $10 \times 2\frac{3}{4}$, RUDDER POST $11\frac{1}{8} \times 8\frac{1}{2}$, STERNPOST $11\frac{1}{8} \times 8\frac{1}{2}$

M.V. SAN ELISEO

LITHGOWS LTD NO 916

MIDSHIP SECTION
AS BUILT

GREENOCK FIRST ENTRY
REPORT NO 20699.

RETAIN



© 2021

Lloyd's Register
Foundation

004769-004777-0271