

Lloyd's Register of Shipping.

Ship's Name "DURHAM" Official No. 163522

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

OK Ship's side scuttles port and starboard sides aft removed and fitted with spigot closing plates in 1950 now removed and fitted with new 12" diam. side scuttles having hinged deadlights, 17 starboard side and 14 port side. Seven new 12" diam side scuttles fitted in sheerstrake starboard side amidships for new Cadets accommodation. The 4" diam. sanitary discharge port side aft removed in 1950, now refitted having suitable storm valve. Two skylights one on shelter deck aft and one on docking bridge aft, closed in 1950, now reopened and fitted with hinging steel cover plates. Three off 12" x 4" gooseneck ventilators removed in 1950 now refitted and supplied with canvas covers. Four off 15" diam. cowl ventilator coamings (1 Port and starboard at after end of No.4 shelter tween deck and forward end of No.5 shelter tween deck) now removed and openings in deck closed with riveted steel spigot plates.

Alex. M. Jenkins.

Surveyor to Lloyd's Register of Shipping,

FALMOUTH.

4th August 1955.

Noted

JMB

2-9-55