

# Lloyd's Register of Shipping.

Ship's Name M.V. "DURHAM" Official No. 163522

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1934.

Shelter tween deck now opened out and vessel restored as an open shelter decker. ✓

Tonnage opening in shelter deck aft opened out and temporary wood covers to same made good. ✓

Original freeing port pass. of tonnage well restored and made workable. ✓

Overboard scupper pass. of tonnage well overhauled and made workable. ✓

Existing control rods from shelter tween deck scuppers removed, storm valves overhauled. Scuppers amidships in shelter tween deck refitted with storm valves on ship's side. ✓

Tonnage openings in fore' bld. of tonnage well and at fore and aft ends of machinery casing refitted with shifting boards in riveted channels. ✓

Other tween deck bulkheads provided with tonnage openings, with portable plates secured by hook bolts. ✓

Drain holes provided in tween deck bulkheads as necessary. ✓

Hatchways on 2<sup>nd</sup> deck examined and cosings, covers, cleats, battens, tarpaulins overhauled as necessary. ✓

Openings in machinery casings in shelter tween deck are to Rule requirements. ✓

Freeboard marks, previously altered now verified. ✓

Fee £5.5-0 (1/6 16 JUL 1946)

C. Little  
June 1946

W. Steal  
18 JUL 1946