

34387

SEP -9 1940

## Lloyd's Register of Shipping.

Ship's Name DURHAM.Official No. 163522.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1934.

- (1). The tonnage opening which was closed October 1939 has now been restored. B.A. beam and wood decking in way removed.
- (2). The riveted steel plates over wash ports in tonnage space removed. Shutters refitted in working condition.
- (3). Welded steel plates over openings in shell plating for overboard scuppers removed. (5 on starb. side and 4 on port. side.) Scuppers in efficient condition.
- (4). Bolted plates at the openings in shelter tween deck bulkheads on frames 92 starb., 91 port., 75 starb. & 66 1/2 port., have been removed and storm boards 3" thick fitted in riveted channels.
- (5). Battening arrangements on shelter tween deck hatchways maintained in efficient condition.

H. Campbell.

2/9/40

Noted  
L.B.

10 SEP 1940