

Surveys for Freeboard - S.S. ~~TOBIAS PARK~~

SEABOARD TRADER

Alterations for Removal of Naval Accommodation and Defence Equipment as required during war emergency.

Ventilators:

1 @ 16", 1 @ 12" and 3 @ 6" removed and holes efficiently plated over in naval accommodation, port, No. 5 tween deck.

2 @ 8" removed and holes efficiently plated over in Ford. Magazine.

Hatches:

1 @ 24" dia., gunners' escape hatch, removed and hole plated over in naval accommodation, starbd., No. 5 tween deck.

1 @ 24" x 24" access to Ford. Magazine removed and hole efficiently plated over.

Sidelights:

9 port and 2 starbd. in naval accommodation, No. 5 tween deck, efficiently plated over.

Storm Valves:

2 port side in naval accommodation located below 2nd deck and extended spindles for control valves and air pipe removed and holes efficiently plated over.

Additions

Ventilators:

One new 12" dia. x .38" x 36" cmg. ventilator fitted to Stewards' Store, starbd. amidships, extending to boat deck and supplied with wood plug and canvas cover.

*Attendant*

8

*dy*



© 2020

Lloyd's Register Foundation