

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

14

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey
Date of Survey **10-8-32**
Name of Surveyor

CANTICK HEAD

Ship's Name. ORIOLE		Port of Registry and Nationality. London	Official Number. 146067	Gross Tonnage. 488.43	Date of Build. 1921	Particulars of Classification. +100A.1.
Number in Register Book						

Registered Dimensions from Register.	LENGTH. 160.2	BREADTH. 25.2	DEPTH. 9.7	UNDER DECK TONNAGE. 316.14
Length on LOADLINE.	160.25	Frame Depth $4\frac{1}{2}$ Rule $\frac{3}{1\frac{1}{2}}$	Ceiling 775 Sheer +91	Peak Tanks 14CL
CORRECTED DIMENSIONS.	160.25	24.95	10.66	316.14

Co-efficient of fineness..... **.74**
Any modification necessary } **CDB**
[Para. 4 (a) to (e)]* }
Co-efficient as corrected **.72**

Sheer { Stem..... **69** } **114** $\div 2 = 57$...Mean **36/33.09**
at { Sternpost..... **45** } **91**

Sheer at $\frac{1}{2}$ of the length from { Stem **41** } **65** $\div 2 = 32.5$...Mean
{ Sternpost **24** } **58.04** $\div 55 = 59.09$

Gradual mean Sheer **26.02** Correction
Standard mean Sheer [Table, Para. 18] **32.02** $\div 4 = 8.07$
Difference..... **-8**

If limited as Para. 18 (f) **-8**

Rise in Sheer { At front of bridge house..... **7\frac{1}{2}**"
from amidships { Para. 18 (e) } At after end of forecastle **36**"

Fall in Sheer {
Para. 18 (d) } $\div 2 =$
Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... **3\frac{1}{2}**"
Correction for Length, if required (Para. 12, 13, and 14)
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 11, 12, 13, and 14) **1'-0\frac{1}{2}"**
Difference **9\frac{1}{4}"**
Percentage as below..... **66.7%**
-6.16

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) **+17.**
Allowance for Deck Erections **5.99.6**

	Length.	Length allowed.	Height.
Forecastle.....	20.0	23-8"	22.08
Bridge House.....	10'-10\frac{1}{2}"	10.87	7-0
† Raised Qr. Dk.....	91-9\frac{1}{4}"	91.77	3'-6"
Poop.....			
Total	124.72		
Length of Ship	160.25		-778
Corresponding percentage } Para. 11, 12, 13, or 14 }	66.70%		

Port of Survey
Date of Survey **10-8-32**
Name of Surveyor

Moulded Depth as measured..... **11'-9"**

Addition for Keel below base line for draught record..... **1\frac{1}{2}"** inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... **160.25**
Length in Table **141.00**
Difference **19.25**
Correction for 10ft., Table A. **.9** Table C.
 \times Difference divided by 10 **1.73** (if required.)
If $\frac{1}{10}$ ths length covered divide by 2 **.86** **= +3\frac{1}{4}"**

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered **.778**
Thickness of usual wood deck, less stringer **2"** **-3"**

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... **25'-0"**
Round of Beam **6\frac{1}{2}"**
Normal round..... **6\frac{1}{4}"**
Difference **\frac{1}{4}"** $\div 2 =$ **\frac{1}{8}"**
Proportion of Deck uncovered (Para. 19) **2.22** $\times \frac{1}{8} =$ **NIL**

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A **1'-8\frac{1}{2}"**
Correction for Sheer **-8**
Correction for Length **+1'-0\frac{1}{2}"**
Allowance for Deck Erections **-6**
Correction for Round of Beam..... **0'-7\frac{1}{4}"**
Correction for fall in Sheer (if any).....
Correction for Steel Deck (if required) **-3**
Additions for non-compliance with provisions of }
Para. 11 (d) and (e) } **0'-4\frac{1}{4}"**
Other Corrections (if any) **HEIGHT OF R.Q.D.** **3'-6**

Winter Freeboard **3'-10\frac{1}{4}"**
Summer Freeboard **3'-8\frac{1}{2}"**
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. } **NIL**

Winter Freeboard from deck line **3'-10\frac{1}{4}"**
Summer " " " **3'-8\frac{1}{2}"**
Indian Summer " " " **3'-6\frac{3}{4}"**
N. A. Winter " " "

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, ~~wood~~ **RAISED QUARTER** Steel Deck:—

Tropical Fresh Water Line above Centre of Disc ...	5\frac{1}{4}	Tropical Fresh Water Freeboard ...	3'-8\frac{1}{2}"	3'-8\frac{1}{2}"
Fresh Water Line " " ...	3\frac{1}{4}	Fresh Water " " ...	3'-3\frac{1}{4}"	3'-3\frac{1}{4}"
Tropical Line " " ...	2\frac{1}{2}	Tropical " " ...	3'-5\frac{1}{4}"	3'-5\frac{1}{4}"
Winter Line below " " ...	1\frac{1}{2}	Winter " " ...	3'-6\frac{1}{2}"	3'-6\frac{1}{2}"
Winter North Atlantic Line " " ...	4"	Winter North Atlantic " " ...	3'-8\frac{1}{2}"	3'-10"

FW = $\frac{987}{40+7.88} = 3.13$

MARKING FOR MARKING FORM
111 JUL 1934
RECEIVED

RECEIVED -6 JUL 1934
RECEIVED SEP 1932

1010-18800-15490

57.8.10.8.32

Lloyd's Register
Foundation