

17 NOV 1943

# Lloyd's Register of Shipping.

Glasgow Rpt No. 67747

Ship's Name

OCEAN STRENGTH.

Official No. 169058.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

## ADDITIONAL TEMPORARY ACCOMMODATION IN NOS 4 AND 5. TWEEN DECKS.

Nº 5. TWEEN DECKS. Two escape hatchways (I.P. & I.S.) 24" x 24" Coamings 30" x 34" filled with hinged steel W.T. covers.

Additional side scuttles filled (4.P. + I.S.) 10" dia with hinged deadlights.

Two ventilators @ 9" dia and <sup>two</sup> @ 6" dia. Coamings 30" x 34" with wood plugs and canvas covers.

Two W.C.s filled with double valves and storm valve on ship's side.

Sink & shower discharges filled with double automatic self-closing valves.

Two hinged W.T. doors (I.P. & I.S.) operated on both sides filled on W.T. Bulkhead aft end of temporary accommodation.

## Nº 4. TWEEN DECKS.

Steel companionway filled on port side of Nº 4 hatchway, bolted to hatch beams. Tarpaulins & ballining down arranged to suit.

Two W.C.s filled on port side "Baltic" type with two valves and storm valve on ship's side.

Wash basin discharges filled with two automatic self-closing valves.

Bath shower discharge filled with valve on ship's side controlled from above the freeboard deck.

Two ventilators 9" dia coamings 30" x 25" filled with wood plugs & canvas covers.

George Lulluhni

Glasgow. 13<sup>th</sup> November 1943.



© 2020

Lloyd's Register  
Foundation



Handwritten initials or mark.

17 NOV 1943

Handwritten text in the left column, likely bleed-through from the reverse side. The text is faint and difficult to decipher but appears to be a continuous paragraph.

Handwritten text in the right column, also likely bleed-through from the reverse side. It continues the narrative or list from the left column.

16 & 17 NOV 1943

