

*Equivalent Mld. Depth to give
Mld. Draught of 21'-4 1/2"*

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

Index No. _____
(For London Office only.)

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey _____
Date of Survey 24/3/26
Name of Surveyor _____

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
<i>Messrs. Jones & Co. S. B. Co.</i>	<i>Yard No. 108 + 109.</i>				<i>+ 100 A. 1. (Contemplated)</i>
Number in Register Book _____					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
Length on LOADLINE.		Frame Depth Rule	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.	<u>347.0</u>			

Moulded Depth *assumed.* 26'-0"
Addition for Keel below base line for draught record.....inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH

Length of Ship on Loadline..... 347.0
Length in Table 312.0
Difference 35.0
Correction for 10ft., Table A. 1.4 Table C. .7
× Difference divided by 10 4.90 (if required.) 2.45
If $\frac{1}{10}$ ths length covered divide by 2 +5" ✓ +2 1/2 ✓

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered422
Thickness of usual wood deck, less stringer 3 1/2" -1 1/2" ✓

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....
Round of Beam
Normal round.....
Difference $\div 2 =$
Proportion of Deck uncovered (Para. 19)

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A 5'-11" ✓
Correction for Sheer -5 1/2" ✓
Correction for Length +5" ✓
Allowance for Deck Erections -9" ✓
Correction for Round of Beam..... ✓
Correction for fall in Sheer (if any)..... ✓
Correction for Steel Deck (if required) -1 1/2" ✓
Additions for non-compliance with provisions of Para. 11 (d) and (e) ‡ 5'-0" ✓
Other Corrections (if any)

Winter Freeboard 5'-0" ✓
Summer Freeboard (3 1/2 - 5) 4'-7 3/4" ✓
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. 26'-0 1/2"
4'-7 3/4"
21'-4 3/4"

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck :—

Fresh Water Line	above centre of Disc
Indian Summer Line	" " "
Winter Line	below " "
Winter North Atlantic Line	" " "

† State dimensions of freeing port area on back of this form.
‡ The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

© 2020 Lloyd's Register Foundation