

Lloyd's Register of Shipping.

Ship's Name T.S.M.S. "PORT DUNEDIN"

Official No. 148599

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Tonnage opening in shelter deck and freeing ports in tonnage well were dealt with at Swansea as per attached Report. *(on board)*

The openings in shell plating from scuppers draining shelter deck spaces have now been permanently closed by steel plates (E.W.) and the tween decks are now efficiently drained to the bilges. ✓

Efficient lifelines have been provided. ✓

Forecastle on Shelter Deck has open passage way in centre 4'-8" wide, hinged steel doors on forecastle front and hinged wood doors to accommodated spaces in forecastle, 12" sills. *(See Swansea Rpt C 11 (contd))* ✓

The statutory deck line has now been cut in at the top of the wood sheathing on shelter deck, the freeboards reassigned, markings cut in and verified. ✓

The tonnages shown on Ship's Register have not been altered.

heat ports in tween decks efficiently closed and made W.T. Syd. 23/9/41. *[Signature]*

SURVEYOR TO LLOYD'S REGISTER.

SYDNEY. N.S.W. 4th June, 1941.

Noted *[Signature]*
-5 AUG 1941