

GLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.

Signal Letters (if any) G.Y.P.M.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164,573.	Fort Amherst.	12 in 1936 London.

No., Date, and Port of Previous Registry (if any). ----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Glasgow.	1936	Blythswood Shipbuilding Company Limited, Glasgow.
Number of Decks ..	Two (and one partial)	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..	314	Tenths. 9
Number of Masts ..	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..	319	3.1
Rigged ..	-----	Main breadth to outside of plating ..	45	1
Stern ..	Cruiser	Depth in hold from tonnage deck to ceiling at midships ..	24	5.5
Build ..	(Side Shell-out & in Bottom Shell-Clinker)	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ..	--	--
Galleries ..	None	Depth from top of beam amidships to top of keel ..	27	5.8
Head ..	None	Depth from top of deck at side amidships to bottom of keel ..	27	2.2
Framework and description of vessel ..	Steel Transverse Passenger & Cargo	Round of beam ..	--	5
Number of Bulkheads ..	Five	Length of engine room, if any ..	51	7.5
Number of water ballast tanks, and their capacity in tons ..	Seven-422			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 5220 Tons.

Ditto per inch immersion at same depth } 25.9 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
One	Steam Direct Acting Vertical Inverted Cylinder Triple expansion.	Engines. British	Engines. 1936	Engines. &	Three			408
No. of Shafts.	Particulars of Boilers. Horizontal Return Tube single ended	Boilers. British	Boilers. 1936	Boilers. David Rowan & Co., Ltd., Glasgow.	22"	39"	----	----
One	Number Two Iron or Steel Steel Loaded Pressure 220 lbs.	British	1936		35"			2400 (estimated)
					63"			13½ knots (---)

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	2476.34	On account of space required for propelling power	1116.32
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	315.20
Turret or Trunk ..	69.89	These spaces are the following, viz.:— Below deck, and in Forecastle, Poop and Round Houses (Number of Seamen or Apprentices for whom accommodation is certified.....83.....).	
Forecastle ..	596.01	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Bridge space ..	334.52	Masters Accommodation 15.22	
Chart House ..	6.31	Chart Space 6.31	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	5.44	Wireless Telegraphy Space 3.67	
Excess of Hatchways ..		Boatswains Stores 18.34	
		Steering Gear Spaces 41.08	
		Water Ballast Spaces 26.37	
Gross Tonnage ..	3488.51	Cubic Metres. 9872.48	
Deductions, as per Contra ..	1542.51	4365.30	110.99
Register Tonnage ..	1946.00	5507.18	1542.51

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 497.78 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 71.55 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Nil.

Name of Master	Certificate of	Service No.	Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Furness Withy & Company Limited Furness House, Leadenhall Street, London.			
Shares:— Sixty-four.			
Dated 24th January, 1936.			



Robinson Irving Dodsworth
of Furness House, Leadenhall St.
E.C.3.—Manager—