

## Lloyd's Register of Shipping.

Ship's Name "HIGHLAND MONARCH"

Official No. 148158.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in

New Hatchway to No. 2 Hold Built on Forecastle Deck Extension.

Description of Hatchway

No. 2


Dimensions of Hatchway

22'-6" x 16'-0"

Coamings

( Ht. above Deck 24"  
( Thickness (sides .44"  
( ends .44"  
( Stiffeners 7" x 3" x .38" BA<sup>S</sup>  
( Brackets, stays 2 @ 1½" solid round stays each side.

Hatch Beams

( Number 5  
( Spacing 4'-1½"  
( Scantling & sketch   
( Bearing surface 3"

12" x 6" x 44 lbs. joist

Fore and afters

None

Hatch Covers

( Material W.P.  
( Thickness 3"  
( How Fitted F & A  
( Bearing surface 3"

Spacing of cleats

22" to 24"

Number of tarpaulins

3

Battens, wedges and tarpaulins have been supplied and are in good condition,  
and in accordance with Rule requirements.

Lashings are provided in accordance with Rule requirements.

*T.R. McIlvenna*

Surveyor to Lloyd's Register of Shipping.

LONDON.

January, 1948.

Notes  
AD  
20.1.48