

15 FEB 1963

41467
14 FEB 1963

Rpt. C. 11 (Contd.)

GLASGOW REPORT No. FBD. 943

Index No. (For London Office use)

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name M.S. "STIRLINGSHIRE" Official No. 168536Port of Registry GLASGOW.This ship has been under survey at GLASGOW.

on 29th Nov., 1962 & 24th Jan., 1963 ~~1963~~ and the following alterations to the conditions of assignment of loadlines have now been effected/~~board~~—

Existing entrance door through engine casing, to refrig. machinery compartment in starboard 'tween decks, permanently closed and E.W. at this time.

New access steel companionway for refrig. machinery compartment fitted on boat deck with jointed W.T., hinged steel door secured by turnbuckles capable of being operated from either side. Doorway coaming 18" high. Access opening in new companionway cut through boat deck over washplace also below in upper deck and vertical gastight steel plate trunk fitted between openings. Deck plating suitably reinforced with E.W. plate doublings in way of openings.

10" Diameter cowl ventilator, complete with rule closing arrangements, fitted on top of new companionway.

Alexander Drysdale

Surveyor to Lloyd's Register.

(ALEXANDER DRYSDALE)

Noted
20/2/63

A copy of this Report ~~has been~~ will be placed on board.



© 2020

Lloyd's Register
Foundation

004887-004892-0216