

Ship No. 338.

PARTICULARS OF FREEBOARD.

Length of Ship on Load Line 211'-0"

Breadth, extreme: 35'-1 $\frac{3}{4}$ "

Depth of hold to freeboard dk. in way of double bottom (11'-7 $\frac{1}{4}$ " to Main Deck
19'-1 $\frac{1}{4}$ " to Awning Deck).

" " " " " ordinary floors

Builded Depth To Main Deck 13'-6" To Awning Deck 21'-0"

Rule. Deck tonnage (717 to Main Deck
1230 to Awning Deck. Droop in tank top 4"

at stem 5'-0"

at 1/8 length abaft stem 2'-9" Block Coef. .78

at stern post 2'-9"

at 1/8 length forward of stern post 1'-6 $\frac{1}{4}$ "

Freeboard Dk. wood covered? Yes (In way of accommodation only)

Height of Freeboard Deck 8 $\frac{3}{4}$ " Length of Beam at gunwale. 35'-0"

Length of forecastle enclosed and height }
" open " } No Forecastle.

bridge house None

Is fore end closed in? -

Is aft end closed in? -

Height of Raised Quarter deck and height None

Height of Raised Poop deck and height None

Is poop closed in at fore end? -

Height of fore peak top at centre above bottom (

" keel or keel line produced (-

Height of aft peak top at centre above bottom)

" keel or keel line produced) -

Form of Ship Even keel

Is deck docked, awning docked, or part awning docked { Complete Superstructure without tonnage opening

Are extra scantlings, give short outline of same { Fore Peak Blkd. to Awning Deck remaining W.T. Blk. to Main Deck.

Is deck docked, height of 'tween decks at side amidships. -

Classed and where 100 A.I. Lloyd's with Freeboard.

Is it a bar or flat plated keel } flat plate Keel.

Depth of former }

Reduced dimensions -

Is it on tank top fitted or not Over Bilges Only.

Is it ceiling fitted or not Yes.

Is it off. of under deck tonnage -



© 2020

Lloyd's Register
Foundation

004900-004905-0185