

s.s. "DJATINEGARA"

Refer cablegram received from the Kobe Surveyors 1.9.54 advising that Owners contemplate Reclassification in Japan after the ship reaches there under her own steam from Indonesia, and requesting us to state the position.

This ship was built at Belfast 1918-12 and then classed BS\*.

In June 1948 the class was suspended for non-compliance with survey requirements.

A provisional class BS\* "Reclassification Contemplated" with "Examined 4,49" Notation was assigned 6,49.

The class BS\* was reinstated 1,50 and the Notation 'ss.Msl. 4,49' assigned.

The class was again withdrawn 7,51 at Owners' request.

The ship was later taken over by new Owners, 3,52, who desired Reclassification, and for this purpose a General Examination was held at Sourabaya 5,52, but Reclassification withheld for completion.

In 1,53 a Special Survey was commenced for Reclassification, at which time no wear and tear repairs were effected although <sup>these</sup> ~~it~~ indicated that the ship was generally showing signs of her age (36 years).

IT IS SUBMITTED the Owners, through the Kobe Surveyors, be informed that to have the ship's character reinstated in the Register Book as formerly, it will be necessary for:-

- (1) The requirements of a SPECIALS URVEY (D) to be complied with, including the drilling of the shell plating amidships, in the vicinity of the peaks, the strength deck amidships and in such parts of the structure where signs of wastage are evident.
- (2) Any major repairs which have been effected to the structure since the ship was disclassed to be specially examined in order to confirm that the materials used are in accordance with the Rules.
- (3) Structural alterations which may have been carried out since the ship's class lapsed and which affect the longitudinal and/or transverse strength of the ship and Register Book particulars to be reported, and
- (4) full particulars of the equipment on board (which should be found or placed in accordance with Rule requirements) including weights and tests of anchors, also length, diameter and tests, etc. of chain cable to be furnished.



© 2020

3.9.54.

Lloyd's Register  
Foundation

004937-004945-0142