

Lloyd's Register of British & Foreign Shipping,

Royal Exchange,

Middlesbrough, 28th November 1902

LLOYD'S REGISTER
LONDON.

REC'D 29 NOV 1902

ANS'D 1/12

The Secretary
Sir

The S.S. "Hektos" of "Helsingfors"
Messrs R Braggs & Sons No 180 is being fitted
with an electric light installation by
"Finska Elektriska A/c." Helsingfors.

It is for cargo purposes only, with fixed
lights in the tween decks and connections
for portable lights.

The cables are
carried through holds and bunkers in
Bergmann pipes of thin brass lined with
insulating material; the pipes being
enclosed in wood casings.

There is no wiring yet done although
the pipes are almost ready for the cables.

I enclose samples of the cables proposed
to be fitted and shall be glad to hear
whether the insulation of same is
considered satisfactory.

I am Sir
Your obedient servant
R. D. Shilston.

Referred to the Chief Ship Surveyor
and the Chief Engineer Surveyor.

Sp. H. K. Loos (Indt.)
(Reliagot Low Indt. 100%)

It is submitted that the Surveyor be
informed that the insulation resistance of
the wires should be in accordance with paragraph
44 of the Rules for Electric Lighting & they should ask
the makers of the installation for a guarantee that the
cables used fulfil these conditions.

With regard to the cables in the holds, these should be
arranged as required by par 11. The wood Casings must be
strongly protected against damage. & the pipes must be
so fitted that water cannot lodge in them.

Am. 1/8/02

1/8/02

1/8/02 J.H.



© 2020

Lloyd's Register
Foundation