

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) 29 JUL 1935

Received at London Office.....

Date of writing Report 5/6/35 When handed in at Local Office 26/7/35 Part of Oslo

No. in Survey held at Oslo Date, First Survey 15/4/35 Last Survey 12/7/1935  
Reg. Book. (Number of Visits.....10)

on the steamer M.V. "HAARON HAUAN"  
Tons (Gross 4582 Net 3205)

Built at Oslo By whom built H. Aker's Red. Verksted Yard No. #64 When built 1934

Owners Ystlandske Petroleumcompagni Port belonging to Oslo

Electric Light Installation fitted by Lönnichsen & Co Contract No. \_\_\_\_\_ When fitted 1935

Is the Vessel fitted for carrying Petroleum in bulk Yes

System of Distribution Two-wire direct current

Pressure of supply for Lighting 110 volts, Heating ✓ volts, Power 220 volts

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second ✓

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding rating Yes, are they compound wound Yes

are they over compounded 5 per cent. \_\_\_\_\_, if not compound wound state distance between each generator \_\_\_\_\_

Where more than one generator is fitted are they arranged to run in parallel Yes, is an adjustable regulating resistance fitted in series with each shunt field Yes

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes

Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators Built on engine room platform

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators \_\_\_\_\_ and \_\_\_\_\_, are the generators protected from mechanical injury and damage from water, steam or oil Yes

are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes

Main Switch Boards, where placed on platform above engine platform

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards \_\_\_\_\_ and \_\_\_\_\_

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework Yes

and is the frame effectively earthed Yes Are the fittings as per Rule regarding:— spacing or shielding of live parts Yes

accessibility of all parts Yes, absence of fuses on back of board position, proportion of omnibus bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Double-pole overload circuit breaker & reversed current trip, and a single pole equalizer switch

Instruments on main switchboard 10 ammeters 3 voltmeters 1 synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system 2 ohm meters

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes



**Cables:** *Single for power twin for light* are the cables insulated and protected as per Tables IV or V of the Rules *Yes*

**Fall of Pressure,** state maximum between bus bars and any point of the installation under maximum load *ab. 1 volt* *Yes*

**Cable Sockets and other connections,** are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *Yes*

**Paper Insulated Cables.** If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *Yes*

**Cable Runs,** are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*

**Support and Protection of Cables,** state how the cables are supported and protected *Cables are secured by clips, spaced as per Rule.*

If cables are run in wood casings, are the casings and caps secured by screws *Yes*, are the cap screws of brass *Yes*, are the cables run in separate grooves *Yes*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *Yes*

**Refrigerated Chambers,** if lights are fitted, are the cables and fittings in accordance with the special requirements *Yes*

**Joints in Cables,** state if any, and how made, insulated, and protected *None*

**Watertight Glands and Deck Tubes,** are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*

**Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made *Lead*

**Earthing Connections,** state what earthing connections are fitted and their respective sectional areas *One pole of the Todd semi-automatic oil fuel installation is earthed, see letter re same.*

are their connections made as per Rule *Yes*

**Alternative Lighting,** are the groups of lights in the propelling machinery space arranged as per Rule *Yes*

**Emergency Supply,** state position and method of control of the emergency supply and how the generator is driven *Yes*

**Navigation Lamps,** are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes*

are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*

has each navigation lamp an automatic indicator as per Rule *Yes*

**Secondary Batteries,** are they constructed and fitted as per Rule *Yes*

**Fittings,** are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *Yes*

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *Fittings for Echo sounding apparatus fitted in pump room gaslight tubing*

where are the controlling switches situated *outside pump room*

**Searchlight Lamps, No. of** *Yes*, whether fixed or portable *Yes*, are their fittings as per Rule *Yes*

**Arc Lamps,** other than searchlight lamps, No. of *Yes*, are their live parts insulated from the frame or case *Yes*, are their fittings as per Rule *Yes*

**Motors,** are their working parts readily accessible *Yes*, are the coils self-contained and readily removable for replacement *Yes*

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *Yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *Yes*

are they protected from mechanical injury and damage from water, steam or oil *Yes* are their axes of rotation fore and aft *Yes*

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type *totally enclosed* if not of this type, state distance of the combustible material horizontally or vertically above the motors *Yes* and *Yes*

**Control Gear and Resistances,** are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *Yes*

**Lightning Conductors,** where lightning conductors are required, are these fitted as per Rule *Yes*

**Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *Yes*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *Yes*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	2	25	220	109	485	Steam Engine		
AUXILIARY	✓							
EMERGENCY	✓							
ROTARY TRANSFORMER	2	25	220	109	1450	altern. current motor		
	2	15	110		1450	brush current		

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. In.	No.	Diameter. In.	In Circuit.	Rate.			
MAIN GENERATOR	3	120	38	1.88 - 2.76	109	280	30 feet	Rubber	Steel tape
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER MOTOR	2	70	19	1.90 - 3.57	75	200	50 ft	Paper	Steel tape
ENGINE ROOM	2	95	37	1.83	130	240	50 ft	Rubber	"
BOILER ROOM	2	15	1	1.38		14			
AUXILIARY SWITCHBOARDS									
Rotary Transf. Motor	3	95	37	1.83	75	240	50 ft		Steel tape
Transf. Gen.	2	120	38	1.88 - 2.76	109	280	50 ft		"
ACCOMMODATION amidships and in poop	2	1.5	1	1.5	6		2500 m.	Rubber	Lead
WIRELESS	2	16	19	1.04	20	75	600 ft.	"	Steel tape
SEARCHLIGHT									
MASTHEAD LIGHT	2	2.5	7	0.67	2	20	50	"	"
SIDE LIGHTS	2	2.5	7	0.67		20	50	"	"
COMPASS LIGHTS	2	1.5	1	1.5	6		200 m.	"	"
POOP LIGHTS	2	1.5	1	1.5	6				
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. In.	No.	Diameter. In.	In Circuit.	Rate.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP	1	2	6	7	1.05	8.2	31	130 ft	Rubber	Steel tape
ENGINE TURNING GEAR	1	2	6	7	1.05	30	31	130 ft	"	"
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS	1	2	6	7	1.05	20	31	130 ft.	"	"
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										
Refrigerator motor	2	10	10	3	0.9 - 2.5	33.5	43	130 ft	Rubber	Steel tape
Separators	2	2	6	7	1.05	18.7	31	120 "	"	"
Grinding machine	1	2	6	7	1.05	6.7	31	130 "	"	"
Grinding	1	2	6	7	1.05	6	31	120 "	"	"
Lathe	2	2	6	7	1.05	20	31	140 "	"	"
Oil fuel automatic motor	1	2	6	7	1.05	3.5	31	130 "	"	"
Rotary motor	1	3	95	37	1.83	75	240	50 "	"	"
"	1	2	70			75	200	50 "	"	"

© 2020

Lloyd's Register Foundation

0269 2/2

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

Elektrifirmaet  
SÖNNICHSEN & Co.  
Havn

Electrical Engineers.

Date 24.7.35

COMPASSES.

Distance between electric generators or motors and standard compass ab. 32 feet.

Distance between electric generators or motors and steering compass ab. 26 feet.

The nearest cables to the compasses are as follows:—

A cable carrying 6 Ampères 13 feet from standard compass 13 feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be insignificant degrees on all course in the case of the standard

compass, and degrees on course in the case of the steering compass.

for AKERS MEK. VERKSTED

G. W. Sleen.

Builder's Signature.

Date 25/7/35

Is this installation a duplicate of a previous case?

If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

The electric installation on this vessel has been examined during the construction and fitting of engines, dynamos, motors, and during fitting of cables, and switch boards. The materials employed appear to be the best, and the workmanship is good. The installation has been carried out in accordance with the approved plans & specification & the Secretary's letters in connection therewith. The installation has been tested as required by the Rules & found to be satisfactory.

It is recommended that this installation be classed in the Society's Register Book.

Noted  
L.V.  
30/7/35.

Total Capacity of Generators 50 Kilowatts.

The amount of Fee ... £ 547.25 } When applied for, 22/7/35  
Travelling Expenses (if any) £ : : } When received, 26/7/35

Prude  
Tubom-Rohr  
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

FRI. 16 AUG 1935

FRI. 11 OCT 1935

Assigned

See Osl 76 4580



© 2020

Lloyd's Register Foundation

Im. 11. 20. — Transfer.  
(The Surveyors are requested not to write on or below the space for Committee's Minute.)